

EXHIBIT A: BID SCHEDULE
"THE LINK"
UTILITIES & STORM

A. GENERAL & EROSION CONTROL

Item No.	Estimated Quantity	Unit	Description of Items	Unit Price	Total Amount
1	1	LUMP SUM	Mobilization, Bonds & Insurance		
2	1	LUMP SUM	SWPPP - Preparation & Implementation		
3	1	LUMP SUM	Establish Vegetation in Disturbed Areas		
4	1	EACH	Construction Entrance		
5	100	L.F.	Rock Berm		
6	1,572	L.F.	Silt Fence		
7	1	EACH	Silt Fence at SET		
8	7	EACH	Inlet Protection		
9	1	LUMP SUM	Remove/Relocate Ex. OHE		
10	4	EACH	Sidewalk Open Cut Repair and Replace		
11	1	LUMP SUM	S 9th Street Open Cut Repair and Replace (Storm 5)		
12	1	LUMP SUM	W Ave V Open Cut Repair and Replace (Storm 6)		
13	1	LUMP SUM	W Ave V Open Cut Repair and Replace (Waterline)		
14	1	LUMP SUM	Demo & Inlet Transitions/Curb Throat at S 9th Street (Storm 5)		
15	1	LUMP SUM	Demo & Inlet Transitions/Curb Throat at W Ave V (Storm 6)		
SUB-TOTAL GENERAL & EROSION CONTROL					

EXHIBIT A: BID SCHEDULE
"THE LINK"
UTILITIES & STORM

B. DRAINAGE

Item No.	Estimated Quantity	Unit	Description of Items	Unit Price	Total Amount
1	3	EACH	3'x3' Area Inlet w/ Concrete Apron		
2	4	EACH	36" Drain Basin w/ Curb Inlet Grate		
3	2	EACH	3'x10' Curb Inlet		
4	1	EACH	4'x4' Junction Box		
5	58	L.F.	18" RCP		
6	70	L.F.	15" HDPE		
7	270	L.F.	18" HDPE		
8	305	L.F.	24" HDPE		
9	97	L.F.	30" HDPE		
10	71	L.F.	36" HDPE		
11	2	EACH	18" 4:1 Precast S.E.T.		
12	1	EACH	30" 4:1 Precast S.E.T		
13	1	EACH	36" 4:1 Precast S.E.T.		
14	1	EACH	24"x15" Tee		
15	2	EACH	18" RCP/HDPE Adapter		
16	1	EACH	30" RCP/HDPE Adapter		
17	1	EACH	36" RCP/HDPE Adapter		
18	317	S.F.	18" Embedded Rock RipRap		
19	1	LUMP SUM	Grading 4:1 Slope to Exposed Pipe (Storm 2)		
20	1	LUMP SUM	Roadside Ditch (Storm 3)		
SUB-TOTAL DRAINAGE					

EXHIBIT A: BID SCHEDULE
"THE LINK"
UTILITIES & STORM

C. WATERLINE

Item No.	Estimated Quantity	Unit	Description of Items	Unit Price	Total Amount
1	1,941	L.F.	8" CL 150/C900 PVC Waterline		
2	40	L.F.	6" CL 150/C900 PVC Waterline		
3	1	EACH	8"x8" Tee w/ Blocking		
4	1	EACH	8"x6" Tee w/ Blocking		
5	5	EACH	8" Gate Valve w/ Blocking		
6	1	EACH	6" Gate Valve w/ Blocking		
7	19	EACH	8" 45° Bend w/ Blocking		
8	1	EACH	6" 45° Bend w/ Blocking		
9	1	EACH	6" 90° Bend w/ Blocking (Cut In & Connect to Existing)		
10	1	LUMP SUM	Connect to Ex. 8" at Tee		
11	1	EACH	8"x8" Tapping Sleeve & Valve w/ Blocking		
12	6	EACH	Fire Hydrant Assembly		
13	9	EACH	Dual Water Service		
14	7	EACH	Single Water Service		
SUB-TOTAL WATERLINE					

D. SEWERLINE

Item No.	Estimated Quantity	Unit	Description of Items	Unit Price	Total Amount
1	51	L.F.	6" SDR 35 Sewer Line		
2	394	L.F.	8" SDR 35 Sewer Line		
3	524	L.F.	12" SDR 35 Sewer Line		
4	7	EACH	4' Diameter Manhole		
5	1	EACH	4' Diameter Doghouse Manhole		
6	1	LUMP SUM	Cut In and Reconnect Ex. 12" Sewerline Upstream of Manhole 1		
7	1	LUMP SUM	Cut In and Reconnect Ex. 12" Sewerline Upstream of Manhole 2		
8	1	LUMP SUM	Cut In and Reconnect Ex. 12" Sewerline Downstream of Manhole 5		
9	174	L.F.	Remove Abandoned 12" Sewer & Backfill		
10	2	EACH	6" Cleanout		
11	19	EACH	Single Sewer Service		
12	1	LUMP SUM	Bypass Pumping		
SUB-TOTAL SEWERLINE					

EXHIBIT A: BID SCHEDULE
"THE LINK"
UTILITIES & STORM

SUMMARY

A. GENERAL & EROSION CONTROL	
B. DRAINAGE	
C. WATERLINE	
D. SEWERLINE	
TOTAL BID	